

SOP-0075 Line Changeover Checklist

Before Changeover

Confirm the current work order is closed in the MES and that all completed units have been moved to the outbound rack.

Retrieve the changeover kit for the incoming part number from the tool crib and verify the kit seal is intact.

During Changeover

Purge all remaining components of the outgoing part number from the line, including feeder bowls and staging trays.

Swap the fixture plates and confirm the datum pins engage without force.

After Changeover

Run three first-off pieces and submit them to quality for dimensional verification before releasing the line to full rate.